

LEGEND :						
		GROUND PIPE H/L				
		SOIL PIPE B/G				
		WASTE PIPE B/G				
		GREASE PIPE B/G				
سررس رسر رس		VENT PIPE HIGH LEVEL				
⊡ FCO		FLOOR CLEAN OUT				
		FLOOR DRAIN				
•	RWO RAIN WATER OUTLET					
V#7.65	 TD	TRENCH DRAIN			•	
		PLUG FOR FUTURE				
—		FLOW DIRECTION				
SWP	SOIL WASTE PIPE		WP	WASTE PIPE		
RWP	RAIN WATER PIPE		VP	VENT PIPE		
TD	TRENCH DRAIN		F/H/L	FROM HIGH LEVEL		
H/L/A	HIGH LEVEL ABOVE		H/L	HIGH LEVEL		
F/L/L	FROM LOW LEVEL		L/L	LOW LEVEL		
IL	INVERT LEVEL		T/A	TO ABOVE		
FFL	FINISH FLOOR LEVEL		T/B	TO BELOW		
B/G	BELOW GROUND		F/A	FROM ABOVE		
B/S	BELOW SLAB		F/B	FROM BELOW		
4	P6-END CLEANOUT		GP	GREASE PIPE		
10	P7-FLOOR CLEANOUT (FINISHED FLOOR AREA)					

NOTE:- EXACT LOCATION WITH DIMENSION WILL BE SUBMITTED IN AS-BUILT STAGE.

2 3

OTES

RAWINGS DIMENSIONS ARE TO BE READ NOT TO BE SCALED.
 ARCHITECTURAL DRAWING MUST BE READ IN CONJUNCTION WITH ALL OTHER SERVICE DRAWINGS AND CONTRACT DOCUMENTS AND IN ACSE OF ANY DISCREPANCIES ARISE BETWEEN THESE DRAWINGS AND ANY OF THE DOCUMENTS. THEY SHOULD BE IMMEDIATELY REPORTED TO THE ENGINEER BEFORE THE COMMENCEMENT OF ANY WORK ON SITE.

WORK ON SILE.

3. ALL THE LEVELS AND DIMENSIONS MUST BE CHECKED AND VERIFIED BY THE MAIN CONTRACTOR BEFORE THE COMMENCEMENT OF ANY ITEM OF WORK ON THE SITE OR THE PREPARATION OF THE SHOP DRAWINGS.

A. THE INVESTOR'S EXTERNAL FACING SHOPFRONT SIGNAGE(IF ANY)
MUST STRICTLY COMPLY WITH THE OWNER'S REQUIREMENTS AND
DIRECTIONS.

NO CHANGES AND/OR PENETRATIONS OF ANY DESCRIPTION WIL PERMITTED TO THE OWNER— PROVIDED EXTERNAL GLASS SHOP

HOUNIS.

6. SUPPLY, STORAGE AND PROTECTION OF EXPANSION JOINT COVERS AND RELATED ACCESSORIES INSIDE ALL INVESTOR SPACES IS BY THE OWNER. INSTALLATION OF THE SAME WILL BE BY THE INVESTOR. SUPPLY AND INSTALLATION OF THE VAPOR BARRIER, FIRE BARRIER & INSULATION DRAPE ASSEMBLY WILL BE BY THE OWNER.

7. This drawing is indicative only (not to be used for construction) and is accurate as at the date shown on the drawing.

R. THIS DRAWING IS SUBJECT TO CHANGE AS PLANNING, DEVELOPMENT AND CONSTRUCTION CONTINUES THROUGH UNTIL OPENING OF THE CENTRE.

OPENING OF THE CENTRE.

9. IT IS THE RESPONSIBILITY OF THE RECIPIENT OF THIS DRAWING TO UPDATE THEMSELVES WITH ANY SUBSCOUENT REVIEWS, UPDATES, ADDITIONS, DELETIONS AND /OR SUBSTITUTIONS.

IO. IT IS THE RESPONSIBILITY OF THE INVESTOR TO UNDERTAKE ON—SITE MEASURE TO VERIFY ALL DIMENSIONS SHOWN ON THIS DRAWING

11. TAMBEN REAL ESTATE CO. DOES NOT ACCEPT ANY LIABILITY
OF ANY FORM FOR THE RECIPIENT'S USE AND/OR INTERPRETATION
OF THIS DRAWING

. The anchor bolt size used for any flooring supporting STEM SHOULD NOT EXCEED MORE THAN 8mm DEPTH TO AVOID IY DAMAGE THAT MAY CAUSED IN THE IMBEDDED PVC CONDUIT.

FOR REVIEW

OWNER



PROJECT TITLE

Al Khiran Outlet Mall

CONSULTANTS

cracknell SS

DESIGN ARCHTE

CALLISONTKL

ENGINEER OF RECO



MANAGED E

TAMDEEN MALL MANAGEMENT CO. K.S.C.C P.O. BOX: 29660 SAFAT 13151, KUWAIT TEL: +965 225362330 FAX: +965 225362360 MALL MANAGEMENT WWW.TAMDEENMALLS.COM

DRAWING TIT

GROUND FLOOR

RESTAURANT - DRAINAGE SYSTEM PLAN

UNIT NO.	G-116			
USAGE.	RESTAURANT			
TRADE	SCALE	DATE		
MECH	1:50 @ A1	NOV 2020		
DRAWN BY	CHECKED BY	APPROVED BY		
DRAWING No.	OF	REV.		
DR-01	06 OF 09	01		

* AS PER SHOP DRAWING